



KENYA ELECTRICITY GENERATING COMPANY PLC

KGN-GDD-199-2021

TENDER FOR SUPPLY & INSTALLATION OF SODA ASH DOSING PUMPS AND UPGRADING OF DOSING PLANT AT OLKARIA I AU 140 MW PLANT (CITIZEN CONTRACTORS)

RFx: 5000008654

19th January, 2022

CLARIFICATION I

In Accordance with the “Tender For Supply & Installation Of Soda Ash Dosing Pumps And Upgrading Of Dosing Plant At Olkaria I AU 140 MW plant” KenGen hereby issues Clarification I as follows;

No.	Bidder's Question	KenGen's Response
	Refer Page 69 Point 3 - " Discharge Pipe from Tank is 54mm Dia. Header, 2ft In Length , whereas at Sketch on Page 73 It Is shown as 73 mm Pipe Header 600 mm long Discharge " - confirm which is correct.	2ft is equal to 600mm, only that, the Units have been inter-changed. The issue then is on the Header Diameter. We clarify that, the Discharge Pipe from Tank is 76 mm Dia. Header, 2ft (600mm) in Length as per the Sketch on page 73.
	We assume the following are included in our scope of supply: A) Hot Dip Galvanized Steel Tank Stand B) Aluminium Chequered Plate 2600 X 2600 X 4mm C) Guard Rail Caging All Around the Tank.	Yes, the items are included in Bidder's scope of supply
	Sketch on Page 71 (Chemical Dosing System) Is Not Legible Please Provide Legible Drawing.	We have scanned and attached a clearer copy as Appendix I .

ACKNOWLEDGEMENT OF CLARIFICATION NO 1.

We, the undersigned hereby certify that Clarification is an integral part of the document and has been incorporated in the Tender proposal.

Signed.....

Tenderer.....

Date.....